

**LOCATION OF WATER SUPPLY RISER FOR FIRE  
PROTECTION SYSTEMS**  
(2020 MSFC)

**General Requirements**

1. The location of the water riser for piping providing water for fire protection systems shall be located as shown in the graphic below.
2. The supply piping shall terminate a minimum of 6-inches above the finished floor but shall not terminate more than 18-inches above finished floor.
  - a. If the riser assembly will be vertical the supply piping shall terminate at 12" above finished floor.
3. A blind cap shall be provided at the top of the riser. The cap shall be supplied by the underground contractor.
4. Reference the handout for Underground Piping for additional information.

